

452.1

Dart Aerospace Ltd.

Date: Monday, 5/15/2006 11:10:41 AM
 User: Kim Johnston

Process Sheet

Customer : CU-DAR001 Dart Helicopters Services	Drawing Name : ARM
Job Number : 27104	
Estimate Number : 11375	
P.O. Number : N/A	Part Number : D33871
This Issue : 5/15/2006 S.O. No. : N/A	Drawing Number : D3387 REV A
Prsht Rev. : NC	Project Number : N/A
First Issue : 5/15/2006 Type : MACHINED PARTS	Drawing Revision : A
Previous Run : 26670	Material : N/A
Written By : SEE COMMENT Below	Due Date : 5/30/2006
Checked & Approved By : 06.05.15	Qty: 20 Um: Each
Comment : Est:A 05.06.10 New Issue KJ/JLM Est:B 06.03.22 Split c'sink op. EC	

Additional Product

Job Number:



Seq. #:	Machine Or Operation:	Description :
----------------	------------------------------	----------------------

1.0	M6061T6B0500X06000	6061-T6 Bar .50" x 6.0"
-----	--------------------	-------------------------



Comment: Qty.: 1.5685 f(s)/Unit Total: 31.3698 f(s)
 6061-T6 Bar .50" x 6.0"
 Material: 6061-T6/T651 (QQ-A-200/8)
 (M6061T6B0.500x06.000)
 Identify for D3387-1
 Batch: ~~11/01/092~~ M/01/092

SD 06.05.26 20

2.0	BAND SAW	BAND SAW
-----	----------	----------



Comment: BAND SAW
 Cut blank: 6.000" x 0.500" x 17.800" long

SD 06.05.26 20

3.0	HAAS1	HAAS CNC VERTICAL MACHINING #1
-----	-------	--------------------------------



Comment: HAAS CNC VERTICAL MACHINING #1
 Machine as per Folio FA511 and Dwg D3387
 Identify as D3387-1
 Tumble and Deburr NO sharp edges

SD/JL 06/05/27 20






4.0	MILLING CONV.	CONVENTIONAL MILLING MACHINE
-----	---------------	------------------------------



Comment: CONVENTIONAL MILLING MACHINE
 C'sink Ø0.375" as per Dwg D3387

JMS 06/05/29 20

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Mfg / Design Mgr	Approval QC Inspector

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Design Mgr	Approval QC Inspector
			Initial Design Mgr	Action Description Design Mgr	Sign & Date			
0605-25	4	1 part C'sink elongated by 0.05. Part off on stopper.		C'sink acceptable. barley shows with screw installed & depth is good.	 06/05/29	 0605-29	 0605-29	 0605-29

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes ☒ No ☐ DQA:  Date: 0605/30

NOTE: Date & initial all entries QA: N/C Closed: _____ Date: _____

Date: Monday, 5/15/2006 11:10:42 AM
User: Kim Johnston

Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: ARM

Job Number: 27104

Part Number: D33871

Job Number:



Seq. #:

Machine Or Operation:

Description :

5.0

QC2

INSPECT PARTS AS THEY COME OFF MACHINE



Comment: INSPECT PARTS AS THEY COME OFF MACHINE

MB 06/05/29 20

6.0

QC8

SECOND CHECK



Comment: SECOND CHECK

mf 06/05/29 20

7.0

PACKAGING 1

PACKAGING RESOURCE #1



Comment: PACKAGING RESOURCE #1

Identify and Stock

Location: WA28

LE 06-05-29 20

8.0

DC

DOCUMENT CONTROL



Comment: DOCUMENT CONTROL

Inspection Level 21

DP 06/05/30 (20)

Job Completion



U 06-05-30

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Mfg / Design Mgr	Approval QC Inspector

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Design Mgr	Approval QC Inspector
			Initial Design Mgr	Action Description Design Mgr	Sign & Date			

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____

NOTE: Date & initial all entries

QA: N/C Closed: _____ Date: _____

DART AEROSPACE LTD		Work Order:	27104
Description: Arm		Part Number:	D3387-1
Inspection Dwg: D3387	Rev: A	Page 1 of 1	

FIRST ARTICLE INSPECTION CHECKLIST

☒ First Article ☐ Prototype

Drawing Dimension	Tolerance	Actual Dimension	Accept	Reject	Method of Inspection	Comments
R0.125	+/-0.010	R.125	/			
0.125	+0.020/-0.000	.126	/			
Ø0.375 x100°	+/-0.010	Ø0.375x100°	/			
R0.032	+/-0.010	R.032	/			
0.500	+/-0.010	.503	/			
0.500	+/-0.010	.496	/			Mat. thickness
7.577	+/-0.010	7.579	/			
R0.125	+/-0.010	R.125	/			
Ø0.507	+0.000/-0.001	Ø.5065	/			
0.250	+/-0.010	.244	/			
1.347	+/-0.010	1.348	/			
2.000	+/-0.010	2.003	/			
1.000	+/-0.010	1.001	/			
Ø0.191	+0.005/-0.000	Ø.192	/			
R0.300	+/-0.010	R.300	/			
2.033	+/-0.010	2.033	/			
0.280	+/-0.010					
0.222	+/-0.010					
1.700	+/-0.010	1.704	/			


Measured by:	SD	Audited by:	J.F.	Prototype Approval:	N/A
Date:	06.05.26	Date:	06/05/26	Date:	N/A

Rev	Date	Change	Revised by	Approved
A	05.04.27	New Issue	KJ/JLM	

DART AEROSPACE LTD
HAWKESBURY, ONTARIO, CANADA

DESIGN	DRAWN BY	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED	APPROVED	DRAWING NO.	REV. A
DATE		D3387	SHEET 1 OF 1
05.01.18		TITLE	SCALE
		ARM	1:3
A		05.01.18	NEW ISSUE

05.03.11



D3387-1 (SHOWN)
D3387-2 (OPPOSITE)

GENERAL NOTES

MACHINE PER DRAWING FILE "D3387-A.DWG"
MATERIAL: 6061-T6 (QQ-A-200/8 OR QQ-A-250/11) 0.500 THICK
(REF DART SPEC. M6061T6B0.500)
DEBURR TO LEAVE R0.030 - 0.063 ON ALL EDGES
TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
ALL DIMENSIONS ARE IN INCHES

**UNCONFINED
SUBJECT TO AMENDMENT
WITHOUT NOTICE**

WORK ORDER
NO. 27104

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL, AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.

Copyright © 2005 by DART AEROSPACE LTD